

Solar Interconnection

Avoid These Common Mistakes



Inspection Passed



Inspection Failed

1. Production Meter Location

When setting up your production meter equipment, make sure it's installed 5 1/2 feet (66 inches) above the finished grade, measured at the meter's center. Additionally, production meter equipment requires 10 feet clearance from LP gas regulators and LP gas tanks.



2. Placard Labeling

Ensure your net and production meter labels are securely attached to the enclosures, with a red background and white lettering as shown in the example.



3. Utility Accessible Disconnect

All PV and battery systems need exterior utility-accessible disconnects for production meters. These disconnects must be combined with the production meter equipment or placed right next to it, within easy reach.



4. Correct Wiring

Confirm with your contractor that the solar is on the line side (top), and the grid power from the panel is on the load side (bottom).



Questions?



interconnection@nhec.com



NHEC Interconnection Team
(800) 698-2007

nhec.com/solar-net-metering